



Bill of Quantities (BOQ) – Residential Building Project



Project Name: 2-Story Residential House



Date: July 14, 2025



Location: Colombo, Sri Lanka

PHASE 1 – SITE PREPARATION

Item No	Description	Unit	Qty	Rate (LKR)	Total (LKR)
1.1	Site clearance (grass, debris)	m ²	500	150	75,000
1.2	Excavation for foundation	m ³	120	600	72,000
1.3	Disposal of excavated material	m ³	100	300	30,000

Subtotal – Phase 1: LKR 177,000

PHASE 2 – SUBSTRUCTURE

Item No	Description	Unit	Qty	Rate (LKR)	Total (LKR)
2.1	Concrete blinding	m ³	15	12,000	180,000
2.2	Reinforced concrete foundation	m ³	30	20,000	600,000
2.3	DPC (Damp Proof Course)	m ²	100	1,200	120,000

Subtotal – Phase 2: LKR 900,000

PHASE 3 – SUPERSTRUCTURE

Item No	Description	Unit	Qty	Rate (LKR)	Total (LKR)
3.1	Brickwork in cement mortar	m ³	90	9,000	810,000

3.2	Reinforced concrete slab	m³	45	18,000	810,000
3.3	RCC Columns & Beams	m³	35	19,500	682,500

Subtotal – Phase 3: LKR 2,302,500

PHASE 4 – FINISHES

Item No	Description	Unit	Qty	Rate (LKR)	Total (LKR)
4.1	Internal plastering (walls)	m²	500	400	200,000
4.2	Floor tiling (ceramic)	m²	300	1,800	540,000
4.3	Painting (2 coats + primer)	m²	700	250	175,000

Subtotal – Phase 4: LKR 915,000

PHASE 5 – SERVICES

Item No	Description	Unit	Qty	Rate (LKR)	Total (LKR)
5.1	Electrical wiring & fittings	Item	1	450,000	450,000
5.2	Plumbing & Sanitary works	Item	1	400,000	400,000
5.3	Water tank installation	Item	1	120,000	120,000

Subtotal – Phase 5: LKR 970,000

 **Grand Total (All Phases): LKR 5,264,500**