

Bill of Quantities - Phase-wise Breakdown

PHASE 1 - SITE PREPARATION

No.	Description	Unit	Qty	Rate (LKR)	Amount (LKR)
1.1	Clearing Vegetation & Debris	m²	450	140	63,000
1.2	Excavation of Topsoil	m³	100	600	60,000
1.3	Site Boundary Marking	Item	1	12,000	12,000

PHASE 2 - SUBSTRUCTURE

No.	Description	Unit	Qty	Rate (LKR)	Amount (LKR)
2.1	Lean Concrete Blinding	m³	12	13,500	162,000
2.2	Reinforced Concrete Footings	m³	25	21,000	525,000
2.3	Damp Proof Membrane	m²	100	400	40,000